KADUR DIVISION.

Dated 2nd April 1930.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Kadur Division, up to 25th April 1930, for constructing quarters for the District Forest Officer at Chikmagalur, Kadur District. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of December 1930.

2. The plans, detailed estimates and conditions may be seen at the Executive Engineer's Office at Chikmagalur between the hours of 11 A.M. and 5 P.M., on working days.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of rupees three hundred in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for Constructing quarters for the District Forest Officer at Chikmagalur," in default of which, tenders will be rejected."

5. The final acceptance of any tender will rest with the Superintending Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor whose tender has been accepted will be posted on the Notice Board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders the earnest money on rejected tenders will be returned.

9. No claims for enhanced rates on any item of work will be allowed after the acceptance of tender.

10. Tenders quoting, as per cent more or less than the estimated rates will not be accepted.

11. Rates should be given both in figures and words.

12. If the dispute arise regarding quality of work and rates the decision of the Chief Engineer is final and legally binding.

Approximate quantities for construction of quarters for the District Forest Officer, at Chikmagalur, Kadur District.

No.	Items of work	Per	Quantity	Rate	
				In figures	In words
	MAIN BUILDING.			Rs.	Rs.
1	Earthwork excavation	C.yd.	90		
2	Filling foundation with stone in mortar ...	C.ft.	2,417		
3	Basement stone in mud	„	1,080		
4	Burnt brick in mud	„	3,627		
4a	Do in chunam	„	746		
5	Burnt stone slab 4" to 6" thick	S.ft.	1,176		
6	Flat arch work in chunam	C.ft.	100		
7	Plastering with chunam ...	Sqr.	64·29		
8	Flooring with 1st class tiles 9" x 9" over 3" concrete bed and cement pointing. (The tiles must be laid diagonally)	„	11·09		
9	Flooring Cuddapah slabs over 3" concrete bed and cement pointing.	„	3·45		
10	Brass terrace roofing ...				

No.	Items of work	Per	Quantity	Ra
				In figures
				Rs.
19	7½" to 9" cornice outside	R.ft.	260	
20	Parapet wall	„	260	
21	Inner cornice 4½" to 6"	„	72	
22	Pointing with cement	Sqr.	4·00	
23	Eave board ornamental	R.ft.	56	
24	Teakwood finials	Each	3	
25	Fixing hip tiles in mortar	R.ft.	18	
26	Whitewashing, two coats	Sqr.	75·65	
27	Zinc sponges	R.ft.	117	
28	Fixing 2½" galvanised pipes	Each	7	
29	Lac varnish 2 coats	Sqr.	10·98	
30	Slate colour painting for outside	„	3·35	
31	Filling basement including consolidation ..	C.yd.	95	
32	Wooden railing in front verandah with painting...	R.ft.	27	
33	Dressing slabs 2 lines	S.ft.	393	
	KITCHEN.			
1	Earth work	C.yd.	41	
2	Stone in mud	C.ft.	1,912	
3	Burnt brick in mud	„	1,915	
4	Do in chunam	„	263	
5	Burnt stone slabs	S.ft.	261	
6	Plastering with chunam	Sqr.	39·61	
7	Flooring with Cuddapah slabs over 3" concrete bed and cement pointing.	„	5·63	
8	Roofing with 1st class Mangalore tiles over teak reepers.	„	16·54	
9	Ridge and hip tiles set in mortar	R.ft.	116	
10	Teadwood work including wood oiling ...	C.ft.	71·94	
11	Eave Board plain	R.ft.	168	
12	Teakwood doors battened complete .	S.ft.	128	
13	Teakwood windows half panelled and half glazed with iron bars.	„	81	
14	Teak cross planks for almirahs	„	21½	
15	Masonry or stone pillars in verandah with base and capital 9' high.	Each	2	
16	Masonry or stone pillars in verandah with base and capital 6" high.	„	2	
17	Wood oiling or lac varnish 2 coats	Sqr.	2·62	
18	Chocolate painting 2 coats	„	3·01	
19	White washing two coats	„	39·61	
20	Flooring with Mangalore tiles over 3" concrete bed and cement pointing.	„	1·70	
21	Fixing 2" pipes	Each	5	
22	Cement pointing to basement	Sqr.	2·40	
23	Sinks bath and kitchen	No.	2	
24	Ventilating tiles bath and kitchen	No.	6	
25	Flooring with burnt stone slabs and cement pointing on 3" concrete to bath.	Sqr.	·50	
26	Coping to connecting walls	R.ft.	28	
	STABLES.			

No.	Items of work	Per	Quantity	Feet	Inches
				Figures wanting	
5	Area work in mud	C.ft.	8		
6	Burnt stone slabs	S.ft.	100		
7	Rough plastering with chunam	Sqr	7687		
8	Roofing with 1st class Mangalore tiles over teak reepers.	„	3 92		
9	Ridge tiles set in mortar	R ft	37		
10	Binding walls at ends of gables	„	28		
11	Mathi or Honney wood work moulding tarring...	C.ft.	28 39		
12	Honney wood door with shutters ..	S.ft.	18		
13	Half window with plank shutters	„	3		
14	Obscouto painting two coats ...	Sqr.	48		
15	Filling basement including consolidation ..	C yd.	6		
16	White washing two coats	Sqr.	16 87		
	COMPOUND WALL.				
1	Compound wall with fence and gate, etc., complete as per design.	R.ft.	300		
2	Extras 2	Lump	sum		

Abstract Notification.

The attention of the public is invited to the notification calling for tenders for construction Anicut across Beraupbena, published on pages 386 to 390 of Part VI of *Mysore Gazette*, dated 3rd April 1930.

The last date for receiving tender is 19th April 1930.

J. A. H. WARDLAW,
Executive Engineer.

MISCELLANEOUS DEPARTMENTS.

GOVERNMENT OF MYSORE, STORES PURCHASE COMMITTEE, BANGALORE.

No. 18187, dated 3rd April 1930.

CONTRACTS PLACED BY THE GOVERNMENT OF MYSORE.

The following contracts were placed by the Stores Purchase Committee, Government of Mysore, during the week ending Good Friday, the 28th March 1930.

Indent number and date	Nature and quantity	Name of firm	Value of contract
I. 1410. Furniture	lot.	(1) Mr. K. [illegible], Mysore.	Rs. 77 [illegible] delivery
		(2) M. S. Sethuramaiya, Bangalore.	Rs. 70 3-2 do
		(3) H. [illegible], Bangalore City.	Rs. 695-2-3 do
		(4) M/s. [illegible], Bangalore City.	Rs. 93-0-0 do
„ 1411. Nitre, N. of K. needle	2½ tons	Mr. I. V. [illegible], Bangalore City.	Rs. 8,734-12-0 f.o.r. Bezwada
„ 1413. Blankets, Hospital	327	Messrs. [illegible], Bangalore City.	Rs. 3,750 6-0 f.o.r. Dharwar
„ 1415. Time Pieces	11	Messrs. [illegible] & Sons, Madras	As [illegible] f.o.r. Trichi
„ 1417. Microscope, [illegible]	..	Mr. [illegible], Bangalore City.	Rs. 309 free delivery
„ 1418. Pressure Gauge, Duplex 7" dial x 100 lbs. pressure.	1	Messrs. T. E. Thomson & Co., Calcutta.	Rs. 150 [illegible]
1419. Cyclostyle Roneo	10/	Messrs. [illegible], Bangalore City.	[illegible]